




Ground Floor




First Floor



Second Floor



Key



Compartment wall

Performance Requirement:

- Fire (Walls & floors)
- 30 Minutes fire protection
- Acoustic (Floors)
- Minimum 43dB Airborne Sound
  - Maximum 64dB Impact Sound
- Acoustic (Walls)
- Minimum 43dB Airborne Sound

Works Notes:

- Supply and install new GypCeiling Lining System to ground floor areas as shown on plan in accordance with manufacturers recommendations. Refer to drawing K-1-04 for details.
- Replace timber clad and mineral fibre ceilings in K102 and K203 with new plasterboard ceilings.
- Upgrade existing stud partitions walls within K003 to meet performance requirements. Refer to K-1-04 for details.
- Replace highlighted doors with new FD30 rated fire doorsets.
- To high-level partition openings where glazing removed in K101 and K201, provide new studwork and board either side with 12.5mm Gyproc WallBoard and Thistle BoardFinish Plaster.
- Replace timber wall paneling with plastered finish within K103.
- All new service penetrations between compartments to be suitably sealed with proprietary fire stopping product.

To be read alongside schedule of works

**Currie & Brown**  
Poseidon House, Neptune Park,  
Maxwell Road, Plymouth, PL4 0SN  
United Kingdom  
Tel: 01752 273473 , Fax: 01752 257755, www.curriebrown.com



Client  
**Council of the Isles of Scilly**

Title  
**Compartment Fire and Acoustic Strategy**

Project  
**Kirklees Refurbishment Works**

Date	01.12.2023	Drawn	AH
Scale	n/a	Checked	KC
Drwg No.	4101565-K-1-03		
Rev			