


EXTRACT FAN SCHEDULE		
REF	FLOW RATE	FAN TYPE
EF1	15L/S	VENT AXIA SILENT FAN HUMIDISTAT MODEL
EF2	30L/S	KITCHEN EXTRACT HOOD SUPPLIED BY OTHERS WITH A MINIMUM PRESSURE DROP OF 30Pa.

LEGEND




© COPYRIGHT EDP:
THIS DRAWING REMAINS THE PROPERTY OF EDP ENVIRONMENTAL.
NOTE: DO NOT SCALE FROM THIS DRAWING. ALL DIMENSIONS SHALL BE CHECKED ON SITE. ONLY FIGURED DIMENSIONS SHALL BE USED. IF IN DOUBT, ASK.
THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL RELEVANT DRAWINGS, DOCUMENTS AND INFORMATION PREPARED BY THE ARCHITECT, OTHER CONSULTANTS AND SPECIALISTS.
THIS DRAWING SHALL BE READ IN CONJUNCTION WITH EDP ENVIRONMENTAL MECHANICAL & ELECTRICAL SERVICES SPECIFICATION & TECHNICAL SCHEDULES

HEALTH & SAFETY
STANDARD CONSTRUCTION HAZARDS THAT A COMPETENT CONTRACTOR WOULD BE AWARE OF DURING NORMAL WORKING PRACTICES ARE NOT IDENTIFIED ON THIS DRAWING.
RISKS THAT MAY NOT BE IMMEDIATELY APPARENT ARE LISTED BELOW.

NOTES

1. MAKE DUE ALLOWANCE FOR PIPEWORK MOVEMENT FROM EXPANSION/CONTRACTION AND TO LIMIT ANY NOISE.
2. FIT DRAIN VALVES AT ALL LOW POINTS IN THE SYSTEM AND AAVS AT HIGH POINTS.
3. ALL SERVICES IN FLOOR VOIDS, CASINGS, DUCTS ETC AND IN PLANT ROOMS SHALL BE INSULATED IN ACCORDANCE WITH CURRENT REGULATIONS.
4. INSULATION ON PIPEWORK TO HAVE A GWP LESS THAN 5.
5. ALL HEATING PIPEWORK AND HEAT SOURCE SHALL BE INSTALLED, TESTED, FLUSHED THROUGH AND COMMISSIONED IN ACCORDANCE WITH BS 6700. HEATING SYSTEM SHALL BE THOROUGHLY FLUSHED WITH CLEAN WATER AND REFILLED USING SENTINEL X100 FLUID IN ACCORDANCE WITH SENTINAL DATA SHEETS AND HEAT SOURCE MANUFACTURERS RECOMMENDATIONS.



P01	30.07.25	FIRST ISSUE
REV	DATE	REVISION DESCRIPTION
SCHEDULE OF REVISIONS		

Architects Model:
Structural Model:
Other Model:
Model Schedule Key: [Discipline] [Date Received] [Revision] [Specific Model Number]



HEAD OFFICE
EMBLEM HOUSE
PYNES HILL
EXETER, EX2 5BA
EXETER T: 01392 367 237
BRISTOL T: 01173 258 975
FAREHAM T: 01329 800 710
LONDON T: 02076 091 899
CHOBHAM T: 01276 300 280

CLIENT:
COUNCIL OF THE ISLES OF SCILLY

PROJECT:
PARK HOUSE, ISLES OF SCILLY
DRAWING TITLE:
VENTILATION LAYOUT
GROUND FLOOR

SERVICE TYPE:
MECHANICAL
DRAWING STATUS CODE:
REVIEW AND COMMENT

SCALE @ A1 1:50	INTERNAL PROJECT REF: 2606
--------------------	-------------------------------

DRAWING NUMBER:
2606-EDP-XX-00-DR-M-2000
PROJECT NUMBER - ORIGINATOR - ZONE - LEVEL - TYPE - ROLE - SEQUENTIAL NUMBER

Designed by:	Drawn by:	Checked by:	Revision:
NO	NO	SO	P01