

Project No. 150457

Client: Council of the Isles of Scilly

Tender Issue 10/11/2017

STRIDE TREGLOWN
ARCHITECTURE

Carn Gwavel School

10 November 2017

This document includes:

Code	Section	Revision	Dated
P12	Fire stopping systems		

Project No. 150457

Client: Council of the Isles of Scilly

Signed Off **Tender Issue 10/11/2017**

P12 Fire stopping systems

GENERAL

PRODUCTS

- 40 MINERAL WOOL RIGID BATTS
- Standard: To BS EN 13162.
 - Manufacturer: PFC Corofil Units 3-4 King George Trading Estate Davis Road Chessington Surrey KT9 1TT
Tel: + 44 (0) 208 391 0533 Fax: + 44 (0) 208 391 2723
Email: sales@pfc-corofil.com
www.pfc-corofil.com.
 - Product reference: PFC Corofil VFB+ Ventilated Fire Barrier.
 - Recycled content: None permitted.

EXECUTION

- 62 EXECUTION GENERALLY
- Gaps: Seal gaps between building elements and services, to provide fire resistance and resist the passage of smoke.
 - Adjacent surfaces: Prevent overrun of sealant or mortar on to finished surfaces.
- 66 INSTALLING MINERAL WOOL BATTS
- Installing batts: Fit tight into void between the penetrating services and the surrounding construction to form a solid barrier.
 - Brackets: To manufactures details.
Bracket fixing: To manufactures details.
 - Face of batts: Flush with the surface of wall, floor or soffit.
 - Joints between batts: To manufactures details.
 - Gaps between services and barrier: Seal with fire resisting sealant.

COMPLETION

- 91 CLEANING
- Masking tapes: Remove.
 - Cleaning: Clean off splashes and droppings. Wipe down finishes.
- 92 INSPECTION
- Notice for inspection (minimum): 3 working days.