

## Materials

The pod will rest on concrete sleepers

Cladding will be Natural finish feather edge cladding (photo)

Windows will be timber & double glazed, finished in a light grey wood stain.

Roof will be sheathed in OSB , covered with a suitable membrane or GRP and finished with a turf roof system (details included)

