Carefully remove modern structure and make surface good for integration with public realm

Carefully remove ramp

Carefully remove window to allow for opening to be blocked up

Carefully remove modern staircase

Remove existing stage. Retain all floor boards for potential reuse in the building as part of the interpretation strategy

Carefully demolish solid internal walls in line with structural engineer's drawings and specifications

Carefully remove modern staircase

Carefully take down all internal partitions

Carefully remove facade wall in line with structural engineer's guidance

 $(\mathbf{1})$ 



