

Demolish 1970s construction

Carefully demolish section of roof to allow for construction of 3 No. sections of flat roof. Take care to protect historic building fabric

Remove section of floor plate to allow insertion of lift and stairs to provide access to the volunteer's room

Carefully remove modern staircase

Remove section of floor plate to allow for installation of new staircase

Any demolition in close proximity to the listed building fabric to be done with care to prevent damage to the Town Hall

Carefully remove all internal partitions

Carefully demolish external wall following guidance from the structural engineer

Carefully remove facade wall in line with structural engineer's guidance

Reslate roof with slates to match existing size and colour due to suspected asbestos. To be confirmed following asbestos survey

Remove 2 No. trusses to create volunteer's room

Carefully remove all duct work within the auditorium


Demolish boiler house, taking care to protect the historic Town Hall wall

**Notes:**  
Drawings are based on survey data and may not accurately represent what is physically present.  
Do not scale from this drawing. All dimensions are to be verified on site before proceeding with the work.  
All dimensions are in millimeters unless noted otherwise.  
Purcell shall be notified in writing of any discrepancies.

**Key**  
Existing Construction  
Demolition


**RECEIVED**  
By Liv Rickman at 4:22 pm, Aug 02, 2023

P2	02/08/23	Amended planning
P1	07/07/23	Drawings issued to planning authority
REV	DATE	DESCRIPTION



CLIENT  
**Council of the Isles of Scilly**

PROJECT  
**Isles of Scilly Cultural Centre and Museum**  
241601



TITLE  
**Planning - Second Floor - Demolition Plan**

SIZE	SCALE	LAST REVISED	DRAWN	CHECKED
A1L	1:50		CM	GC

REV P2 SUITABILITY/REASON FOR ISSUE **PLANNING**

DRAWING NUMBER  
**IOS-PUR-01-02-DR-A-0132**

**1 Demolition - Second Floor**  
1:50